

T-Sheet Code References:

- BA-20** - Internal metal balustrade to new metal stair with integrated stringer and metal handrail.
- BA-21** - Internal metal balustrade to existing stair with replaced stringer and metal handrail.
- BA-22** - Wall mounted handrail.
- CL-XX** - Ceiling finishes to soffit of stairs as per interior designer's details.
- FL-XX** - Floor finish to Interior Designer's details.
- FL-XX** - Step nosing to Interior Designer's details.
- IW-XX** - Painted plasterboard finish.
- SR-01** - New metal framed stair with screed stair pans. For vinyl / carpet finish.
- WF-XX** - Wall finishes to stairs.

- Plant Parapet  
52015
- Plantwell Parapet  
50815

- Roof Terrace Proposed FFL  
49285

- 8th Proposed FFL  
45505

- 7th Proposed FFL  
41690

- 6th Proposed FFL  
37640

- 5th Proposed FFL  
33590

- 4th Proposed FFL  
29570

- 3rd Proposed FFL  
25550


- 2nd Proposed FFL  
21530

- 1st Proposed FFL  
17145


- Ground Proposed FFL  
12760

- LG Proposed FFL  
8380

- Basement FFL  
4340



1 Proposed Section 1 - South Building Core 2  
1:100 at A1



2 Proposed Section 2 - S.B Core 2  
1:100 at A1

SR-01 - New metal framed stair with screed stair pans. For vinyl / carpet finish.

BA-20 - New metal stringer with integrated balustrade to new metal stair. Balustrading to not shown for clarity. Refer to typical balustrade detail ST-01.


BA-21 - New metal stringer with integrated balustrade. Balustrading to not shown for clarity. Refer to typical balustrade detail ST-01.

WF-XX - Wall finishes to interior designer's details. Refer to ST-01

CL-XX - Soffit finishes to stair to interior designer's details. Refer to ST-01

Existing survey information is incomplete, all staircases to be surveyed prior to the balustrade manufacture.

FL-XX - Floor finishes to interior designer's details. Refer to ST-01.



3 Key Plan  
1:1000 at A1

GENERAL NOTES.

© Buckley Gray Yeoman Limited

All dimensions to be checked on site prior to commencement of any works, and/or preparation of any shop drawings.

Sizes of and dimensions to any structural elements are indicative only. See structural engineers drawings for actual sizes / dimensions.

Sizes of and dimensions to any service elements are indicative only. See service engineers drawings for actual sizes and dimensions.

This drawing to be read in conjunction with all other Architect's drawings, specifications and other Consultants' information.

All proprietary systems shown on this drawing are to be installed strictly in accordance with the Manufacturers/Suppliers recommended details.

Any discrepancies between information shown on this drawing and any other contract information or manufacturers/suppliers recommendations is to be brought to the attention of the Architect

DO NOT SCALE FROM THIS DRAWING.

NOTES.

Staircase drawings to be read in conjunction with 1046-CO and 1046-ST.

To be read in conjunction with 1046-Outline specification.

For typical staircase detail refer to 1046-ST-01.

Balustrade, handrail and soffit treatment remain consistent to all stairs. Refer to Interior's Designer's for all individual wall and floor finishes within each core.

For Staircase and Core Finishes refer to Interior Designer's drawings including:

- Stringer
- Balustrade
- Balustrade handrail
- Wall mounted handrail
- Wall finishes / skirting
- Floor finishes
- Stair nosings
- Lighting

Signage to be developed in Stage 04.

P1 30/04/21 Stage 03 issue

JT

REV. DATE

NOTE

DRAWN

**BGY**

BUCKLEY GRAY YEOMAN  
+ 44 20 7033 9913  
BGY.CO.UK

CLIENT

**Whitefriars Limited**

PROJECT

**65 Fleet Street**

DRAWING

**Proposed Core 2  
Stair Sections**

SCALE

**1:100 @ A1**

**(1:200 @ A3)**

DATE

**Apr. 2021**

DWG No.

**1046-ST-07**

REVISION

**P1**

STATUS

**Stage 03**

APPROVED

**RO**

