

2ND FLOOR FIT OUT PLAN DRAWING (1/2)

General pavements:

PAV 1
Solus Ceramics, AU.GMR.050 Anthracite Bright, 300x600 mm, R9 slip rating.

PAV 2
15 mm painted parquet, Bergland-parkett Ash Technograu Trend-Epoca 2400x140x15 mm, glued Installation with SikaBond-T54.

PAV 3
Solus Ceramics, Altai 2CPD809, Off White, 100x100 mm.

General walls:

EWL 1
~~Glazed Balustrade, Laminated (extra clear low-iron) glass.~~ (OMITTED)

EWL 2
Acoustic laminated safety glass.

EWL 3
12.5 mm double layer of standard plasterboard painted white RAL 9010.

EWL 4
12.5 mm sound resistant double layer of plasterboard painted white RAL 9010.

EWL 5
12.5 mm moisture resisting double layer of plasterboard painted white RAL 9010.

EWL 6
Solus Ceramics, Altai 2CPD809, Off White, 100x100 mm.
12.5 mm moisture resisting double layer of plasterboard.

EWL 7
Wall coverings to define.
12.5 mm sound resistant double layer of plasterboard.

EWL 8
12.5 mm sound resistant double layer of plasterboard.

EWL 9
30 mm Kemmlit duct panel, Noxx TR, white 9095.

IWL 1
70 mm Lightweight metal stud at 600 mm centers.

IWL 2
70 mm Lightweight metal stud at 600 mm centers.
67mm Acoustic partition slab between studs.

IWL 3
50 mm Lightweight metal stud at 600 mm centers.

IWL 4
50 mm Lightweight metal stud at 600 mm centers.
47mm Acoustic partition slab between studs.

IWL5
90 mm Lightweight metal stud at 600 mm centers.
67mm Acoustic partition slab between studs.

General ceilings:

CEI 1 - 2ND FLOOR
Suspended ceilings system.
Standard plasterboard painted white RAL 9010.

CEI 1 - 3RD FLOOR
Suspended ceilings system.
12.5 mm double layer of standard plasterboard painted white RAL 9010.

CEI 2
Suspended ceilings system.
Moisture resisting plasterboard painted white RAL 9010.

CEI 3
Suspended ceilings system.
Plasterboard painted white RAL 9010 (Sound resistant double layers of 12.5 mm each side).
100 mm Acoustic partition slab between light steel joists.

CEI 4
Ceiling tiles 600x600x15 mm, Rockfon Pacific® range, E edge detail.
Rockfon White pre-finished.

CEI 5
Metal suspended ceiling 900x250x30 mm, SAS International.
Polyester powder coated in standard range White RAL 9010.

Separation between ceramic tiles and parquet flooring with Schluter - SCHIENE, stainless steel.
Movement joints with Schluter ® - DILEX EKSN, movement zone on synthetic rubber.
All visible steel plates coated in white RAL 9010.

REVISION	DATE	DESCRIPTION
H	19.11.08	TYPICAL FLOOR DETAILS REFERENCE

CONSTRUCTION

AUDI WEST LONDON LONDON, UK	DATE: NOV 08 SCALE: 1:50@A1	1.3
2ND FLOOR INTERNAL FINISHES PLAN 1/2 CONSTRUCTION DRAWINGS	ASSIST.: FERNANDO CARLOTA	
ATMB13 arquitectos lda R. Ricardo Espírito Santo, 9, cv. dta., 1200 790 Lisboa, tel.: 21 3931244, fax: 21 3931249	RESP.: MIGUEL BELEZA	

REPRODUÇÃO TOTAL OU PARCIAL RESERVADA À ENTIDADE PROMOTORA PARA OS FINS E NOS TERMOS CONTRATUAIS. PROPRIEDADE INTELECTUAL E DIREITOS DE AUTOR DE ATMB13, ARQUITECTOS, LDA. DECRETO LEI 63 / 85 (14 MARÇO)

Do not Scale. Used figured dimensions only. All dimensions to be checked on site.

All drawings to be read in conjunction with the Engineers' drawings. Any discrepencies between consultants drawings to be reported to the Architect before any work commences.