

FINISHES SCHEDULE Project: Pillar & Lucy House Project Number: 2500 Issue: 03 Date: 19/05/2008											
LOCATION		WALL FINISHES		NOTES	CEILING FINISHES		NOTES	FLOOR FINISHES		NOTES	REV
ROOM NAME	ROOM NUMBER	MATERIAL VM = Vinyl matt emulsion paint T = Ceramic tile B = Sandblasted brickwork C = Walnut timber cladding to existing columns	COLOUR Eggshell from Dulux Trade range MDF skirting to match wall colour Ceramic tiles by H & R Johnson, Prismatics range		MATERIAL VM = Vinyl matt emulsion paint S = Suspended perforated metal tile B = Sandblasted brickwork	COLOUR		MATERIAL C = Heavy Duty Carpet tile L = Static dissipating linoleum sheeting P = Painted Screed S = Stone Paving T = Porcelain stone floor tile	COLOUR		

TENANCY 112A STORAGE	B-001	VM	61YY86/041		VM	61YY86/041		S	-	Existing flagstones relayed	
TENANCY 112A	B-002	VM B	61YY86/041		VM B	61YY86/041		S	-	Existing flagstones relayed	
TENANCY 112A	B-003	VM B	61YY86/041		VM B	61YY86/041		S	-	Existing flagstones relayed	
LANDLORD TENANCY	B-004	VM	61YY86/041		VM	61YY86/041		S	-	Existing flagstones relayed	
LANDLORD TENANCY	B-005	VM	61YY86/041		VM	61YY86/041		S	-	Existing flagstones relayed	
LANDLORD TENANCY	B-006	VM	61YY86/041		VM	61YY86/041		S	-	Existing flagstones relayed	
TENANCY 112A	B-007	VM	61YY86/041		VM	61YY86/041		S	-	Existing flagstones relayed	

ESCAPE STAIRS	G-001	-	-		-	-		-	-		
TENANCY 112	G-002	VM B	61YY86/041		VM	61YY86/041		-	-		
TENANCY 112	G-003	VM B	61YY86/041		VM	61YY86/041		-	-		
RISER 1	G-004	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	
SERVICES RM TENANT	G-005	E	61YY86/041		VM	61YY86/041		L	3139		
SERVICES RM LANDLORD	G-006	E	61YY86/041		VM	61YY86/041		L	3139		
SERVICES RM LANDLORD	G-007	E	61YY86/041		VM	61YY86/041		L	3139		
OFFICE ENTRY LOBBY	G-008	E B	61YY86/041 -		VM	61YY86/041		C	303482		

TENANCY 1A	1-001	VM B	61YY86/041		VM	61YY86/041		C	303482		
MAIN LOBBY	1-002	VM B	61YY86/041		VM	61YY86/041		C	303482		
TEA ROOM 1	1-003	T	PRS15		VM	61YY86/041		T	DIT04		
CLEANERS CUPBOARD	1-004	T	PRS15		VM	61YY86/041		T	DIT04		
DISABLED WC 4	1-005	T	PRS15		VM	61YY86/041		T	DIT04		
WC 3	1-006	T	PRS15		VM	61YY86/041		T	DIT04		
RISER 1 & 2	1-007	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	

FINISHES SCHEDULE		Project: Pillar & Lucy House Project Number: 2500 Issue: 03 Date: 19/05/2008									
LOCATION		WALL FINISHES		NOTES	CEILING FINISHES		NOTES	FLOOR FINISHES		NOTES	REV
ROOM NAME	ROOM NUMBER	MATERIAL VM = Vinyl matt emulsion paint T = Ceramic tile B = Sandblasted brickwork C = Walnut timber cladding to existing columns	COLOUR Eggshell from Dulux Trade range MDF skirting to match wall colour Ceramic tiles by H & R Johnson, Prismatics range		MATERIAL VM = Vinyl matt emulsion paint S = Suspended perforated metal tile B = Sandblasted brickwork	COLOUR		MATERIAL C = Heavy Duty Carpet tile L = Static dissipating linoleum sheeting P = Painted Scream S = Stone Paving T = Porcelain stone floor tile	COLOUR		

WC 2	1-008	T	PRS15		VM	61YY86/041		T	DIT04		
WC 1	1-009	T	PRS15		VM	61YY86/041		T	DIT04		
RISER 6	1-010	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	
CORRIDOR	1-011	VM B	61YY86/041		VM	61YY86/041		C	303482		
RISER 3	1-012	VM	61YY86/041		VM	61YY86/041	Fire stopping to service penetrations - Hilti Fire Batts	L	3139	Fire stopping to service penetrations - Hilti Fire Batts	
IT ROOM	1-013	VM	61YY86/041		VM	61YY86/041		L	3139		
TENANCY 1B	1-014	VM B	61YY86/041		VM	61YY86/041		C	303482		
TENANCY 1D	1-015	VM B	61YY86/041		VM	61YY86/041		C	303482		
RISER 5	1-016	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	
CORRIDOR	1-017	VM B	61YY86/041		VM	61YY86/041		C	303482		
ESCAPE STAIRS	1-018	-	-		-	-		-	-		
TENANCY 3C	1-019	VM B	61YY86/041		VM	61YY86/041		C	303482		
RISER 4	1-020	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	

TENANCY 2A	2-001	VM B	61YY86/041		VM	61YY86/041		C	303482		
MAIN LOBBY	2-002	VM B	61YY86/041		VM	61YY86/041		C	303482		
TEA ROOM 1	2-003	T	PRS15		VM	61YY86/041		T	DIT04		
DISABLED WC 4	2-004	T	PRS15		VM	61YY86/041		T	DIT04		
WC 3	2-005	T	PRS15		VM	61YY86/041		T	DIT04		

FINISHES SCHEDULE Project: Pillar & Lucy House Project Number: 2500 Issue: 03 Date: 19/05/2008											
LOCATION		WALL FINISHES		NOTES	CEILING FINISHES		NOTES	FLOOR FINISHES		NOTES	REV
ROOM NAME	ROOM NUMBER	MATERIAL VM = Vinyl matt emulsion paint T = Ceramic tile B = Sandblasted brickwork C = Walnut timber cladding to existing columns	COLOUR Eggshell from Dulux Trade range MDF skirting to match wall colour Ceramic tiles by H & R Johnson, Prismatics range		MATERIAL VM = Vinyl matt emulsion paint S = Suspended perforated metal tile B = Sandblasted brickwork	COLOUR		MATERIAL C = Heavy Duty Carpet tile L = Static dissipating linoleum sheeting P = Painted Screed S = Stone Paving T = Porcelain stone floor tile	COLOUR		

RISER 1 & 2	2-006	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	
WC 2	2-007	T	PRS15		VM	61YY86/041		T	DIT04		
WC 1	2-008	T	PRS15		VM	61YY86/041		T	DIT04		
RISER 6	2-009	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	
CORRIDOR	2-010	VM B	61YY86/041		VM	61YY86/041		C	303482		
IT ROOM	2-011	VM	61YY86/041		VM	61YY86/041		L	3139		
RISER 3	2-012	VM	61YY86/041		VM	61YY86/041	Fire stopping to service penetrations - Hilti Fire Batts	L	3139	Fire stopping to service penetrations - Hilti Fire Batts	
TENANCY 2B	2-013	VM B	61YY86/041		VM	61YY86/041		C	303482		
RISER 5	2-014	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	
TENANCY 2D	2-015	VM B	61YY86/041		VM	61YY86/041		C	303482		
CORRIDOR	2-016	VM B	61YY86/041		VM	61YY86/041		C	303482		
ESCAPE STAIRS	2-017	-	-		-	-		-	-		
TENANCY 2C	2-018	VM B	61YY86/041		VM	61YY86/041		C	303482		
RISER 4	2-019	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	

MAIN LOBBY	3-001	VM B	61YY86/041		VM	61YY86/041		C	303482		
CORRIDOR	3-002	VM B	61YY86/041		VM S	61YY86/041 RAL9010		C	303482		
TEA ROOM 1	3-003	T	PRS15		VM	61YY86/041		T	DIT04		
TEA ROOM 2	3-004	T	PRS15		VM	61YY86/041		T	DIT04		
DISABLED WC 4	3-005	T	PRS15		VM	61YY86/041		T	DIT04		

FINISHES SCHEDULE		Project: Pillar & Lucy House Project Number: 2500 Issue: 03 Date: 19/05/2008									
LOCATION		WALL FINISHES		NOTES	CEILING FINISHES		NOTES	FLOOR FINISHES		NOTES	REV
ROOM NAME	ROOM NUMBER	MATERIAL VM = Vinyl matt emulsion paint T = Ceramic tile B = Sandblasted brickwork C = Walnut timber cladding to existing columns	COLOUR Eggshell from Dulux Trade range MDF skirting to match wall colour Ceramic tiles by H & R Johnson, Prismatics range		MATERIAL VM = Vinyl matt emulsion paint S = Suspended perforated metal tile B = Sandblasted brickwork	COLOUR		MATERIAL C = Heavy Duty Carpet tile L = Static dissipating linoleum sheeting P = Painted Screed S = Stone Paving T = Porcelain stone floor tile	COLOUR		

WC 3	3-006	T	PRS15		VM	61YY86/041		T	DIT04		
RISER 1 & 2	3-007	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	
WC 2	3-008	T	PRS15		VM	61YY86/041		T	DIT04		
WC 1	3-009	T	PRS15		VM	61YY86/041		T	DIT04		
RISER 6	3-010	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	
RISER 3	3-011	VM	61YY86/041		VM	61YY86/041	Fire stopping to service penetrations - Hilti Fire Batts	L	3139	Fire stopping to service penetrations - Hilti Fire Batts	
IT ROOM	3-012	VM	61YY86/041		VM	61YY86/041		L	3139		
TENANCY 3B	3-013	VM B	61YY86/041		VM	61YY86/041		C	303482		
TENANCY 3D	3-014	VM B	61YY86/041		VM	61YY86/041		C	303482		
CORRIDOR	3-015	VM B	61YY86/041		VM	61YY86/041		C	303482		
ESCAPE STAIRS	3-016	-	-		-	-		-	-		
TENANCY 3C	3-017	VM B	61YY86/041		VM	61YY86/041		C	303482		
TENANCY 3A	3-018	VM B	61YY86/041		VM	61YY86/041		C	303482		
MEETING ROOM	3-019	B	-		VM	61YY86/041		C	303482		
OFFICE	3-020	B	-		VM	61YY86/041		C	303482		
OFFICE	3-021	VM B	61YY86/041		VM	61YY86/041		C	303482		
RISER 4	3-022	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	
RISER 5	3-023	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	

TENANCY 4A	4-001	VM B	61YY86/041		VM	61YY86/041		C	303482		
------------	-------	---------	------------	--	----	------------	--	---	--------	--	--

FINISHES SCHEDULE Project: Pillar & Lucy House Project Number: 2500 Issue: 03 Date: 19/05/2008											
LOCATION		WALL FINISHES		NOTES	CEILING FINISHES		NOTES	FLOOR FINISHES		NOTES	REV
ROOM NAME	ROOM NUMBER	MATERIAL VM = Vinyl matt emulsion paint T = Ceramic tile B = Sandblasted brickwork C = Walnut timber cladding to existing columns	COLOUR Eggshell from Dulux Trade range MDF skirting to match wall colour Ceramic tiles by H & R Johnson, Prismatics range		MATERIAL VM = Vinyl matt emulsion paint S = Suspended perforated metal tile B = Sandblasted brickwork	COLOUR		MATERIAL C = Heavy Duty Carpet tile L = Static dissipating linoleum sheeting P = Painted Scream S = Stone Paving T = Porcelain stone floor tile	COLOUR		

LANDING	4-002	VM B	61YY86/041		VM	61YY86/041		C	303482		
BOILER ROOM	4-003	VM B	61YY86/041		VM	61YY86/041		L	3139	Fire stopping to service penetrations - Hilti Fire Batts	
FLUE ROOM	4-004	VM B	61YY86/041		VM	61YY86/041		L	3139	Fire stopping to service penetrations - Hilti Fire Batts	
TENANCY 4B	4-001	VM B	61YY86/041		VM	61YY86/041		C	303482		
TEA ROOM	4-006	T	PRS15		VM	61YY86/041		T	DIT04		
WC	4-007	T	PRS15		VM	61YY86/041		T	DIT04		
RISER 1	4-008	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	
MAIN LOBBY	4-009	VM	61YY86/041		VM	61YY86/041		C	303482		
RISER 6	4-010	-	-		-	-	Fire stopping to service penetrations - Hilti Fire Batts	-	-	Fire stopping to service penetrations - Hilti Fire Batts	
TENANCY 4C	4-011	VM B	61YY86/041		VM	61YY86/041		C	303482		
ESCAPE STAIRS	4-012	-	-		-	-		-	-		