



NOTES

The Contractor is to check all dimensions and conditions on site before commencing. Do not scale from this drawing.

This drawing remains the copyright of POZZONI LLP

All new entrance and internal doors to achieve a minimum effective door width in accordance with Approved Document M, table 2 & diagram 9.

Where doors are double, ensure that clear opening widths are achieved whilst 1 door leaf is in closed position.

All to enable disabled access.

Laminate faced doors to be set in painted softwood frames.

Flush painted doors to be set in softwood frames. (colour tba).

All doors to have exposed, flush maple hw lippings all round.

All timber frame sizes are indicative only and contractor to check openings on site prior to fabrication.

Contractor to check all structural opening sizes / wall widths on site prior to fabrication.

Refer also to Door schedules & NBS specification.

Doors to wet areas to be GRP doors and frames; refer to specialist details.

Room / Door Signs (by others, unless otherwise advised):

Rooms signs to be located centrally on (at a height of 1700mm above FFL) or above doors - exact location to be agreed on site.

- ☐ Feasibility
- ☐ Design
- ☐ Tender
- ☐ Contract
- ☒ Construction
- ☐ As Built

Client	Serco Leisure Operating Limited
Job	Standard Details
Drawing	Door Elevations & Details

Scale	nts	@ A3
Drawn	SS	
Date	21/01/05	Rev
Drg. No.	Serco - 012	B

POZZONI	
T 0161 928 7848	2 Woodville Road
F 0161 926 9428	Altrincham
E architects@pozzoni.co.uk	WA14 2FH

B Door type D added. SS 8/07/09
Notes amended

A Notes amended SS 25/6/09