Story	ID	NBS Clause	Location	Door Type	Ironmongery set	Wall Type	Wall Thickness	Structural Opening (W x H)	Handing	Fire Rating	Acoustic Rating	Finish / Colour	Operation Type
Ground Floor													
	D0-02-01	25-50-20/120	Access WC	D TypeA2	Set 01	P-TypeA	102	1,010x2,100	L		30Rw	Laminated / TBC	
	D0-03-01	25-50-20/120	Interview Room	D TypeA1	Set 04	P-TypeA	102	1,010x2,100	R		30Rw	Laminated / TBC	
	D0-04-01	25-50-20/120	Head Teacher's Office	D TypeA1	Set 04	P-TypeA	102	1,010x2,100	L		30Rw	Laminated / TBC	
	D0-06-01	25-50-20/120	Hygiene	D TypeA2	Set 01	P-TypeA	102	1,010x2,100	L		30Rw	Laminated / TBC	
	D0-07-01	25-50-20/120	Central Stock	D TypeA3	Set 06/FR	P-TypeA	102	810x2,100	R	FD30S		Laminated / TBC	
	D0-08-01	25-50-20/120	Circulation	D TypeC4	Set 09	P-TypeA	102	1,800x2,100	DD	FD30S		Laminated / TBC	Hold Open
	D0-09-01	25-50-20/120	Cleaners	D TypeA2	Set 06/FR	P-TypeA	102	1,010x2,100	R	FD30S		Laminated / TBC	
	D0-12-01	25-50-20/120	Circulation	D TypeC4	Set 08	P-TypeA	102	1,800x2,100	DD	FD30S		Laminated / TBC	Access Control - Hold Open
	D0-14-01	25-50-20/120	Reception classroom	D TypeB1	Set 01/FR	P-TypeC	110	1,500x2,100	L	FD30S	30Rw	Laminated / TBC	
	D0-14-02	25-50-20/185	Reception classroom	Moving Wall Type B	as supplied	P-TypeC + P-TypeH	277	5,450x2,400	-		55 Rw	Laminated / TBC	
	D0-15-01	25-50-20/120	Reception classroom	D TypeA1	Set 01/FR	P-TypeA	102	1,010x2,100	L	FD30S	30Rw	Laminated / TBC	
	D0-17-01	25-50-20/120	Infant classroom	D TypeB1	Set 01/FR	P-TypeA	102	1,500x2,100	L	FD30S	30Rw	Laminated / TBC	
	D0-20-01	25-50-20/120	Infant classroom	D TypeB1	Set 01/FR	P-TypeA	102	1,500x2,100	R	FD30S	30Rw	Laminated / TBC	
	D0-21-01	25-50-20/145	General Office	Roller Shutter Type B	as supplied	P-TypeA	102	2,050x2,700	-			Laminated / TBC	
	D0-22-01	25-50-20/120	Entrance	D TypeC6	Set 08	P-TypeA	102	2,650x2,700	DD			Laminated / TBC	Access Control
	D0-23-01	25-50-20/120	Small Hall	D TypeC2	Set 03	P-TypeA	102	1,800x2,100	DD		30Rw	Laminated / TBC	
	D0-23-02	25-50-20/120	Small Hall	D TypeD3	Set 10	P-TypeH	97	1,500x2,100	DD			Laminated / TBC	
	D0-24-01	25-50-20/120	Main Hall	D TypeD1	Set 03	P-TypeA	102	1,500x2,700	DD		30Rw	Laminated / TBC	Hold Open
	D0-24-02	25-50-20/185	Main Hall	Moving Wall Type A	as supplied	P-TypeF + P-TypeH	535	7,800x2,700	-		55 Rw	Laminated / TBC	
	D0-25-01	25-50-20/120	Multi Store	D TypeC5	Set 05/FR	P-TypeD	122	1,800x2,100	L	FD60S		Laminated / TBC	
	D0-28-01	25-50-20/145	Kitchen	Roller Shutter Type A	as supplied	P-TypeD	122	3,944x1,375	-	FD60S	18 Rw	Laminated / TBC	
	D0-28-02	25-50-20/120	Kitchen	D TypeA1	Set 01/FR	P-TypeD	122	1,010x2,100	R	FD60S	30Rw	Laminated / TBC	
	D0-28-03	25-50-20/120	Kitchen	D TypeA2	Set 01	P-TypeA	102	1,010x2,100	L			Laminated / TBC	
	D0-28-04	25-50-20/120	Kitchen	D TypeA3	Set 06	P-TypeA	102	810x2,100	R			Laminated / TBC	
	D0-28-05	25-50-20/120	Kitchen	D TypeA3	Set 06	P-TypeA	102	810x2,100	R			Laminated / TBC	
	D0-32-01	25-50-20/120	Circulation	D TypeD2	Set 09/FR	P-TypeA	102	1,500x2,100	DD	FD30S		Laminated / TBC	Hold Open
	D0-32-02	25-50-20/120	Circulation	D TypeC4	Set 08/FR	P-TypeA	102	1,800x2,100	DD	FD30S		Laminated / TBC	Access Control - Hold Open
	D0-34-01	25-50-20/120	Junior classroom	D TypeB1	Set 01/FR	P-TypeA	102	1,500x2,100	L	FD30S	30Rw	Laminated / TBC	
	D0-37-01	25-50-20/120	Junior classroom	D TypeB1	Set 01/FR	P-TypeA	102	1,500x2,100	R	FD30S	30Rw	Laminated / TBC	
	D0-38-01	25-50-20/120	Group room	D TypeB2	Set 01/FR	P-TypeA	102	2,400x2,100	R	FD30S	30Rw	Laminated / TBC	
	D0-39-01	25-50-20/120	Junior classroom	D TypeB1	Set 01/FR	P-TypeA	102	1,500x2,100	L	FD30S	30Rw	Laminated / TBC	
	D0-42-01	25-50-20/120	Junior classroom	D TypeB1	Set 01/FR	P-TypeA	102	1,500x2,100	R	FD30S	30Rw	Laminated / TBC	
	D0-43-01	25-50-20/120	Maintenance Store	D TypeA3	Set 06/FR	P-TypeA	102	810x2,100	L	FD30S		Laminated / TBC	
	D0-45-01	25-50-20/120	Store / Future lift	D TypeA2	Set 01/FR	P-TypeA	102	1,010x2,100	R	FD30S		Laminated / TBC	
	D0-47-01	25-50-20/120	Circulation	D TypeD1	Set 03/FR	P-TypeD	122	1,500x2,700	DD	FD60S	30Rw	Laminated / TBC	Access Control - Hold Open
	D0-48-01	25-50-20/120	Lobby	D TypeD2	Set 09/FR	P-TypeA	102	1,500x2,100	DD	FD30S	30Rw	Laminated / TBC	Hold Open
	DS0-01-01	25-50-20/120	Stair	D TypeC1	Set 08/FR	P-TypeA	102	1,800x2,700	DD	FD30S		Laminated / TBC	Access Control - Hold Open

© Penoyre & Prasad LLP

Do not scale from this drawing.
Dimensions are to be verified on site prior to construction

Ordnance Survey Data reproduced by permission of Ordnance Survey®, on behalf of Her Majesty's Stationery Office. © Crown Copyright. All rights reserved.

Rev	Date	Prep/Check	Description
C01	01.08.16	PM /ALG	Updated further to BB comments
P02	07.07.16	ALG /RM	Updated and reissued for Tender
P01	23.02.16	ALG /RM	First Issue for Draft CP's

Penoyre & Prasad

28-42 Banner Street
London EC1Y 8QE

020 7250 3477
penoyreprasad.com

Client
Balfour Beatty

Project
DRET London Free School - Primary

Drawing Title
Internal Door Schedule - Page 1

Drawing Status
For Construction

Date
23.02.2016

Scale
n/a

Drawing Number

project	originator	zone	level	type	role	number
DPS	PPA	00	XX	DR	A	92401

Revision
C01